

BID SCHEDULE

ITEM No.	DESCRIPTION OF WORK	EST. QTY.	UNIT	UNIT PRICE	TOTAL COST
1	Mobilization		LS		
2	Construction Support Tasks		LS		
3	Survey		LS		
4	Time and Materials Work	1	T&M	\$50,000	\$50,000
5	Clearing and Grubbing		LS		
6	Clear and Grub Eucalyptus Trees		LS		
7	Construct Unclassified Fill (Import)		CY		
8	Scarify and Recompact Subgrade (Per Detail 1/C-4)		SF		
9	0.35' AC over 0.5' CMB & Geogrid (Per Detail 1/C-4)		SF		
10	Settlement Monument Vault (Per Detail 5/C-4)		EA		
11	Settlement Monument and Monument Vault (Per Detail 5/C-4)		EA		
12	6" AC Curb / Std. Plan 120-1 D1-150 (Per Detail 4/C-4)		LF		
13	Raise/Lower Existing Vaults to Grade (Per Detail 4/C-5)		EA		
14	8-foot Chain Link Fence w/ Barbed Wire		LF		
15	8' Metal Rolling Gate w/ Appurtenances		EA		
16	Install Type Q Markers Per CalTrans Std. Plan A73A		EA		
17	Install Type D Markers Per CalTrans Std. Plan A20A		EA		
18	PCC Drainage Swale (Per Detail 2/C-4)		LF		
19	Metal Flume Downdrain w/anchors (Per Detail 6/C-5)		LF		
20	McCarthy Inlet		EA		
21	Rip Rap Pad w/PCC Cut-off Wall (Per Detail 2/C-5)		EA		
22	8-Foot Precast Concrete Wall w/ Metal Terrace (Per Detail 5/C-5)		LF		
23	Bollard (Per Detail 6/C-5)		EA		
24	Chain Link Swing Gate		EA		
25	LFG Trench (Per Detail 7/C-4)		LF		
	ELECTRICAL DESCRIPTION OF WORK				
26	Pole		EA		
27	Light		EA		
28	Install Pole & Light		LS		
29	Install & Wire for Controllers		LS		
30	Base		LS		
31	Conduit		LS		
32	Power from SCE		LS		
33	Labor		EA		
SAN BERNARDINO INTERNATIONAL AIRPORT AIRPORT RE-DEVELOPMENT PROJECT				TOTAL:	